



Shuklagandaki Municipality
Office of Municipal Executive
Dulegaunda, Tanahun

Bid Addendum Notice

(Notice Publication Date: 09 October, 2024)


This Bid Addendum Notice is published to notify to all interested Bidders that the Addendum published on 1st October, 2024 for IFB / RFP / EOI / PQ No. 3/NCB/WORKS/SMC/2081-082, Project Title Upgrading of Mankauri Motor Marga has attached an extra Addendum Document Type named as "Addendum Version 0" automatically generated by the system which was an error with the publication date as "09-09-2024 10:52" which does not belong to the related Bid Document. So, please do not consider that error Addendum Document type. Also, please take only in consideration the Following Bill of Quantity attached with this notice and the Addendum done for Last Date of Bid Submission is "21st October, 2024 12:00" and the Bid Opening Date is "21st October, 2024 14:00".

Chapter: Bill of Quantities

1 Provisional Sum						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	PROJECT HORDING BOARD: Supplying and installation of hording board specifying brief of project as per specified size, shape and other details all complete.	PS	1	5000.00	5000.00	
2	INSURANCE: Insurance of works, construction equipments and against accident to workmen including third party insurance.	PS	1	75000.00	75000.00	
3	ADDITIONAL LABORATORY TEST: Additional lab testing of materials, specimen, mix design etc. not considered in item rate(specification) as instructed by Engineer if required.	PS	1	30000.00	30000.00	

1 Provisional Sum						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate(in words)	Amount(in NPR)
1	Earthwork: Roadway excavation in all types of soil as per Drawing and technical specification including removal of stumps and other deleterious matters, all lifts and lead as per Drawing and instruction of the Engineer	Cum.	3570.41			


Chief Administrative Officer



SL. No	Item Description	Unit	Quantity	Bidder's Rate (in words)	Amount (in NPR)
2	Stone Soling : Filling by stones in the foundation and levelling including haulage distance upto 30m	Cum.	764.03		
3	P.C.C:Cement Concrete Works (1:2:4) in foundation It includes mixing,placing in position, vibrating, compacting,finishing,curing and all other incidents.	Cum.	693.11		
4	"Plum wall: Providing and laying Plum Concrete (Boulder Mixed Concrete) as per drawing and specifications				
5	60% M15 concrete and 40% boulder/stone using Mechanical Means with form works "	Cum.	289.65		
6	Hume pipe : Providing and laying RCC hume pipe 24" diameter-NP3 as per specified size, quality, standard, drawing and specifications including all requirements	Nos.	20.00		
7	Gabion Work : Providing and laying machine made and mechanically selvedged double twist hexahonal mesh products wire mesh 10*12/2.7/3.4/ZN Gabion jali as per specified size, quality, standard, drawing and specifications including all requirements	Sqm.	4249.00		
8	Assembling Gabion boxes: Assembling mechanical woven Gabion boxes / mattresses, placing in position including stretching; forming compartments; tying the sides and diaphragms with binding wire in each mesh; tying with bracing wires and tie wires; and tying down the lid complete as per specification	Sqm.	4249.00		
9	Gabionbox filling: Providing and filling stone/ boulder in gabion boxes/ mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications.	Cum.	800.00		

Handwritten signature

Chief Administrative Officer

Chief Adminiatriative Officer